

Northline Restoration Co.

2614 S Bellington Ave
Philadelphia, PA 19145
Phone: (215) 555-0167

Project: 946 Alderwick St
Philadelphia, PA 19145
Rehabilitation Budget & Scope of Work

Trade	Description of Work	Total Cost (\$)
Northline Restoration Co. will complete a full renovation of the property, beginning with demolition and removal of the existing roof membrane, selected interior wallboard, outdated kitchen components, damaged mechanical materials and all construction debris. Work includes framing a new first-floor powder room, installing a high-efficiency HVAC system, replacing the flat main roof with a fully waterproofed roofing assembly, installing a new kitchen with cabinets and countertops, laying luxury vinyl plank flooring, completing plumbing and fixture upgrades, painting the full interior and performing final construction cleanup.		
Demolition & Removal	Remove existing roof membrane, kitchen components, damaged drywall and abandoned mechanical materials. Haul debris from property. Includes dumpster and disposal fees.	\$10,500
Roofing	Install new modified bitumen roof system, drip edge, flashing and fascia repairs.	\$9,500
HVAC	Install new high-efficiency heating and cooling system, ductwork and thermostats.	\$8,500
Flooring	Repair subfloor where needed and install LVP flooring throughout the house.	\$5,500
Drywall	Install and finish new drywall on walls and ceilings where existing wallboard is removed.	\$5,500
Framing	Install new framing and blocking where required, including first-floor powder room.	\$2,500
Kitchen	Install new cabinets, countertops, sink, faucet and backsplash.	\$11,000
Painting	Prime and paint walls, ceilings and trim, two finish coats.	\$4,500
Plumbing	Install new water and drain lines for kitchen and powder room and replace basement water heater.	\$5,000
TOTAL PROJECT COST:		\$62,500